



- 4" CONC. SIDEWALK (2521)
- 3" AGGREGATE BASE, CL. 5 (2211)
(100% CRUSHED LIMESTONE OR RECYCLED CONCRETE OR BITUMINOUS)
(INCIDENTAL TO WALK)
- SUBGRADE PREPARATION (2112) (INCIDENTAL)

NOTES:

1. MINNESOTA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION SHALL APPLY. CONCRETE MIX 3A32 WILL BE REQUIRED.
2. SIDEWALKS: REFERENCE SECTION 2521, AGGREGATE BASE: REFERENCE SECTION 2211
3. 1/2" PRE FORMED JOINT FILLER MATERIAL-AASHTO M213 REQUIRED AT THE INTERSECTION OF ALL MAINLINE WALK WITH STATIONARY OBJECTS. (I.E., BUILDING FOUNDATION, EXISTING WALK, ETC.) (NOT REQUIRED WHEN CURB AND GUTTER OR WALK ARE ADJACENT TO BITUMINOUS PAVEMENT.)
4. PLACE 1/2" EXPANSION JOINT AT 100 FT. INTERVALS FOR SIDEWALK.
5. CONCRETE WALK CONSTRUCTION JOINTS SHALL BE TOOLED OR SAW CUT AT 6 FT. INTERVALS.
6. SIDEWALK EDGES SHALL BE ROUNDED WITH 1/4" RADIUS TOOL.

CONCRETE WALK
NOT TO SCALE
SAINT PETER STANDARD
PLATE 1003

**CONCRETE WALK
TYPICAL SECTION**

STANDARD DETAIL
PLATE NO:
1003

APPROVED: ADOPTED BY CITY COUNCIL ON JANUARY 12, 2004

REVISED: REVISION ADOPTED BY CITY COUNCIL ON MAY 12, 2014

REMARKS:

SAINT PETER UTILITY STANDARD DETAIL

