

- 1. ALL JOINTS SHALL BE SAW CUT TO A DEPTH OF  $1\frac{3}{16}$ ".
- 2. TRAIL CENTERLINE JOINT SHALL BE SAW CUT.
- 3. TRANSVERSE JOINTS SHALL BE SAW CUT AT 5 FT. INTERVALS.
- 4. TRAIL EDGES SHALL BE ROUNDED WITH  $\frac{1}{4}$ " RADIUS TOOL.
- 5.  $\frac{1}{2}$ " EXPANSION JOINT SHALL BE CONSTRUCTED AT MAXIMUM 100 FT. INTERVALS.

## **CONCRETE TRAIL**

NOT TO SCALE

SAINT PETER STANDARD PLATE 1005

## **CONCRETE TRAIL**

STANDARD DETAIL PLATE NO:

1005

APPROVED: ADOPTED BY CITY COUNCIL ON MAY 14, 2012

REVISED: REVISION ADOPTED BY CITY COUNCIL ON APRIL 14, 2014

**REMARKS:** 

SAINT PETER UTILITY STANDARD DETAIL



2.15 Cate 2000 (1912 6.2)