NOTES:

- 1. PROVIDE AND INSTALL HEALTHY PLANT MATERIALS THAT MEET ALL SPECIFICATIONS AND ARE OF THE SIZE, TYPE AND SPECIES NAMED ON THE PLANT SCHEDULE AND SHOWN ON THE PLANS.
- 2. DIG PLANT HOLE 1'-0" MINIMUM LARGER ON ALL SIDES THAN ROOT BALL.
- PRIOR TO PLACING TREE, SCARIFY BOTTOM AND SIDES OF THE PLANTING HOLE.
- WATER THOROUGHLY AND ADD BACK FILL AS NEEDED AFTER MOISTURE IS ABSORBED.
- 5. BUILD SOIL DIKE AROUND PERIPHERY OF TREE TO HOLD WATER.
- 6. AFTER SETTLEMENT, MULCH WITH MINIMUM 4" LAYER SHREDDED BARK, WOOD CHIPS OR AS OTHERWISE SPECIFIED. DO NOT PLACE MULCH OVER THE ROOT COLLAR.
- 7. REMOVE DEAD OR DAMAGED BRANCHES RETAINING THE NATURAL FORM OF THE TREE.

BAG & BALL PLANTING NOTE:

- REMOVE WRAPPING AND ALL TIES OR STRAPS. IF ROOT BALL IS WRAPPED IN BURLAP REMOVE TOP 1/3 OF BURLAP
 & WIRE FROM ROOT BALL. SYNTHETIC WRAP MUST BE REMOVED AND PROPERLY DISPOSED.
- 2. LOOSEN ROOTS TO ENSURE THEY ARE NOT GIRDLING THE ROOT BALL.
- 3. SALVAGE AND REUSE ALL SOIL THAT CAME WITH THE ROOT BALL.
- 4. WATER THE ROOT BALL PRIOR TO PLACING IT IN THE HOLE.
- 5. IF TREE IS CONTAINER GROWN, SALVAGE ALL SOIL AND MIX WITH SUPPLEMENTED SOIL FOR BACK FILL.

CONIFEROUS TREE PLANTING

NOT TO SCALE

(REFER TO ANSI A300 PART 6/BMP)

SAINT PETER STANDARD PLATE 9005

CONIFEROUS TREE PLANTING

STANDARD DETAIL PLATE NO:

9005

APPROVED: ADOPTED BY CITY COUNCIL ON APRIL 09, 2018

REVISED:

REMARKS:

SAINT PETER UTILITY STANDARD DETAIL



© Bolton & Menk, Inc. 2018, All Rights Reserved H:\STPE_Detail Plates\9005stpe.dwg 4/10/2018 4:17 PM