


SECTION B-B THROUGH APRON

NOTES:

- 1. SEE "PEDESTRIAN CURB RAMP" DETAIL AND PLANS FOR PLACEMENT OF PEDESTRIAN CURB RAMP.
- SLOPE OF DRIVEWAY TO PROPERTY LINE MAY VARY IF NO SIDEWALK IS REQUIRED.
- MINNESOTA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION SHALL APPLY. CONCRETE MIX 3A32 WILL BE REQUIRED.
- 4. SIDEWALKS: REFERENCE SECTION 2521, CURB & GUTTER: REFERENCE SECTION 2531, DRIVEWAYS: REFERENCE SECTION 2531, AGGREGATE BASE: REFERENCE SECTION 2211
- 5. CONTRACTOR SEE PLANS FOR PLACEMENT OF WALK AND DIMENSIONS FOR CONSTRUCTION OF DRIVEWAYS.
- 6. 1/2" PRE FORMED JOINT FILLER MATERIAL-AASHTO M213 REQUIRED AT THE INTERSECTION OF ALL MAINLINE WALK WITH STATIONARY OBJECTS. (I.E., BUILDING FOUNDATION, EXISTING WALK, ETC.) (NOT REQUIRED WHEN CURB AND GUTTER OR WALK ARE ADJACENT TO BITUMINOUS PAVEMENT.)
- 7. CONCRETE DRIVEWAY PAVEMENT IS NOT TO BE POURED MONOLITHICALLY WITH CURB AND GUTTER.
- 8. DRIVEWAY OPENINGS SHALL BE A MAXIMUM OF 24' FROM BOTTOM OF 3' TAPER TO BOTTOM OF 3' TAPER.
- 9. 1/2" EXPANSION JOINT. PLACED AT 100 FT. INTERVALS FOR SIDEWALK.
- 10. CONTRACTION JOINT (FORMED OR SAWED)

SECTION C-C THROUGH APRON



SECTION A-A THROUGH WALK

- 11. IF A 6' (FT) WIDE WALK IS ADJACENT TO BACK OF CURB, THEN THE CURB TAPER SHALL BE 10' (FT) IN LENGTH. IF A WALK ADJACENT TO BACK OF CURB IS WIDER THAN 6' (FT) AND CONTAINS A MINIMUM OF 6' (FT) WALKING AREA AT 2% CROSS SLOPE, THE CURB TAPER SHALL BE 6' (FT) IN LENGTH. * SEE DETAIL 7020A
- CONCRETE WALK CONSTRUCTION JOINTS SHALL BE TOOLED OR SAW CUT AT 6 FT. INTERVALS.

RESIDENTIAL CONCRETE WALK AND APRON

NOT TO SCALE
SAINT PETER STANDARD
PLATE 7020R

RESIDENTIAL CONCRETE WALK AND APRON

STANDARD DETAIL PLATE NO:

7020R

APPROVED: ADOPTED BY CITY COUNCIL ON JANUARY 12, 2004

REVISED: REVISION ADOPTED BY CITY COUNCIL ON FEBRUARY 27, 2017

REMARKS:

SAINT PETER UTILITY STANDARD DETAIL

