


NOTES:

1. ALL JOINTS SHALL BE SAW CUT TO A DEPTH OF 1³/₁₆".
2. TRAIL CENTERLINE JOINT SHALL BE SAW CUT.
3. TRANSVERSE JOINTS SHALL BE SAW CUT AT 5 FT. INTERVALS.
4. TRAIL EDGES SHALL BE ROUNDED WITH 1/4" RADIUS TOOL.
5. 1/2" EXPANSION JOINT SHALL BE CONSTRUCTED AT MAXIMUM 100 FT. INTERVALS.

CONCRETE TRAIL
 NOT TO SCALE
 SAINT PETER STANDARD
 PLATE 1005

CONCRETE TRAIL	STANDARD DETAIL PLATE NO: 1005
APPROVED: ADOPTED BY CITY COUNCIL ON MAY 14, 2012	 CITY OF Saint Peter <small>NICOLLET COUNTY, MINNESOTA</small> <small>WHERE HISTORY & PROGRESS MEET</small>
REVISED: REVISION ADOPTED BY CITY COUNCIL ON FEBRUARY 27, 2017	
REMARKS:	
SAINT PETER UTILITY STANDARD DETAIL	

Y:\STPE\1005spe.dwg